



Unit 26 Ullenwood Court
Cheltenham GL53 9QS
01242 528444
www.peakhire.co.uk
contact@peakhire.co.uk

FESTIVAL ELECTRICS METHOD STATEMENT

Generators

Generator mounted on road tow trailer. To be positioned on site by towing vehicle on level solid ground. Banksman to assist with manoeuvring. Trailer brakes to be applied. Vehicle unhitched. Trailer locked to prevent unauthorised movement. Generator to be enclosed by security fencing supplied by organisers. Earth rod installed and connected. Outgoing cable to be connected in compliance with relevant Electrical Standards. Generator started, electrical supply tested. RCD protection device tested.

Site Lighting

Floodlights to be mounted upon organiser erected poles by means of mechanical device requiring tools. Access to pole by self supporting combination ladder. Cableways to be kept off public access routes or buried or protection supplied by event organisers.

Marquee Electrical Supplies

Emergency lights to be hung over venue access points using cable ties. Cables to be installed wherever possible at wall/roof junction and securely over doorways. Site harness festoon cable to be hung end to end with as many supporting positions as the structure allows. Empty lampholders to be sealed with pvc tape. Cableways to be tidy and removed as far as possible from public access.